

**Work Order ID 114930**

Monday, March 17, 2014 2:32:17 PM

**\*114930\***

Page 1

Item ID: D3535-23

Revision ID:

Item Name: Stainless Steel Wearplate Center Fwd

Start Date: 3/17/14 Start Qty: 24.00

Required Date: 3/17/14 Req'd Qty: 24.00

Reference:

Accept

**\*N900040100\***Setup Start **\*NS1\***Stop **\*NS2\***

Cust Item ID:

Customer:

Approvals: Process Plan: MLJ Date: 14-03-18

QC: \_\_\_\_\_ Date: \_\_\_\_\_

Tooling: \_\_\_\_\_ Date: \_\_\_\_\_

SPC (Y/N): \_\_\_\_\_ Date: \_\_\_\_\_

Run Start **\*NR1\***Stop **\*NR2\***

Sequence ID/ Work Center ID	Operation Description	Set Up/ Run Hours	Tool ID	Tool #	Plan Code	Accept Qty	Reject Qty	Reject Number	Insp. Stamp
--------------------------------	--------------------------	----------------------	---------	--------	--------------	---------------	---------------	------------------	----------------

Draw Nbr

Revision Nbr

D3535

Rev B

100

**\*100\***

Waterjet

FLOW CNC Waterjet

304.0405

FLOW WATER JET

Memo

1-Cut as per Dwg D3535 Dwg Rev: B Prog Rev: B 2-  
Deburr if necessary

0.00

0.00

28 0 Jm 14-03-23

110

**\*110\***

QC

Quality Control

QC2- Inspect parts off machine FAI/FAIB

Memo

0.00

0.00

28 0 Jm 14-03-23

120

**\*120\***

QC

Quality Control

QC8- Inspect parts - second check

Memo

DAS  
0.00  
27  
9-89

14/3/24

0.00

26 \_\_\_\_\_

DQA: \_\_\_\_\_ Date: \_\_\_\_\_

**WORK ORDER NON-CONFORMANCE / UPDATE**

QA Closed: \_\_\_\_\_ Date: \_\_\_\_\_

Work Order update only ☐

Work Order: _____  Part No. _____  NCR No. _____	<b>DISPOSITION</b>  Rework <input type="checkbox"/> Scrap <input type="checkbox"/> Use-as-is <input type="checkbox"/> Suspected Unapproved <input type="checkbox"/>	<b>AGAINST DEPARTMENT/PROCESS</b>  <table style="width:100%;"> <tr> <td>Skid-tube <input type="checkbox"/></td> <td>Crosstube <input type="checkbox"/></td> <td>Water Jet <input type="checkbox"/></td> <td>Engineering <input type="checkbox"/></td> </tr> <tr> <td>Machining <input type="checkbox"/></td> <td>Small Fab <input type="checkbox"/></td> <td>Prod. Eng. Coord. <input type="checkbox"/></td> <td>Quality <input type="checkbox"/></td> </tr> <tr> <td>Thermoforming <input type="checkbox"/></td> <td>Finishing <input type="checkbox"/></td> <td>Rec/Store/Packaging <input type="checkbox"/></td> <td>Other <input type="checkbox"/></td> </tr> <tr> <td>Large Fab <input type="checkbox"/></td> <td>Composite <input type="checkbox"/></td> <td>Supplier <input type="checkbox"/></td> <td></td> </tr> </table>	Skid-tube <input type="checkbox"/>	Crosstube <input type="checkbox"/>	Water Jet <input type="checkbox"/>	Engineering <input type="checkbox"/>	Machining <input type="checkbox"/>	Small Fab <input type="checkbox"/>	Prod. Eng. Coord. <input type="checkbox"/>	Quality <input type="checkbox"/>	Thermoforming <input type="checkbox"/>	Finishing <input type="checkbox"/>	Rec/Store/Packaging <input type="checkbox"/>	Other <input type="checkbox"/>	Large Fab <input type="checkbox"/>	Composite <input type="checkbox"/>	Supplier <input type="checkbox"/>	
Skid-tube <input type="checkbox"/>	Crosstube <input type="checkbox"/>	Water Jet <input type="checkbox"/>	Engineering <input type="checkbox"/>															
Machining <input type="checkbox"/>	Small Fab <input type="checkbox"/>	Prod. Eng. Coord. <input type="checkbox"/>	Quality <input type="checkbox"/>															
Thermoforming <input type="checkbox"/>	Finishing <input type="checkbox"/>	Rec/Store/Packaging <input type="checkbox"/>	Other <input type="checkbox"/>															
Large Fab <input type="checkbox"/>	Composite <input type="checkbox"/>	Supplier <input type="checkbox"/>																

Root Cause	Date	Step	Qty	Description of work order update or non-conformance	Initial Chief Eng	Action Description	Sign & Date	Verification	QC Inspector
Design <input type="checkbox"/>									
Doc/Data <input type="checkbox"/>									
Equip/Tooling <input type="checkbox"/>									
Handling/Pre <input type="checkbox"/>									
Material <input type="checkbox"/>									
Operator <input type="checkbox"/>									
Offset/Setup <input type="checkbox"/>									
Process <input type="checkbox"/>									
Supplier <input type="checkbox"/>									
Training <input type="checkbox"/>									
Transport <input type="checkbox"/>									
Unapproved <input type="checkbox"/>									

**FAULT CATEGORY**

<b>Landing Gear</b> <input type="checkbox"/> Bending <input type="checkbox"/> Centre Not Concentric <input type="checkbox"/> Cracks <input type="checkbox"/> Crimp/Kink/Ripple/Wave <input type="checkbox"/> Cuffs <input type="checkbox"/> Crushing <input type="checkbox"/> Heat Treat <input type="checkbox"/> Inspection Strip in Tube <input type="checkbox"/> Marks/Chatter <input type="checkbox"/> Turning Sequence <input type="checkbox"/> Wave/Twist in Tube	<b>General</b> <input type="checkbox"/> Bend <input type="checkbox"/> BOM/Route <input type="checkbox"/> Broken/Damage/Defect <input type="checkbox"/> Burrs <input type="checkbox"/> Contamination <input type="checkbox"/> Countersink <input type="checkbox"/> Cut Too Short <input type="checkbox"/> Drawing <input type="checkbox"/> Drill Holes <input type="checkbox"/> Finish <input type="checkbox"/> Fit/Function	<input type="checkbox"/> Folio/Program <input type="checkbox"/> Grain <input type="checkbox"/> Hardware <input type="checkbox"/> Inspection Incomplete/Unqualified <input type="checkbox"/> Instructions Incomplete/Unclear <input type="checkbox"/> Misaligned/off center <input type="checkbox"/> Mislabeled <input type="checkbox"/> Misread <input type="checkbox"/> Off-set <input type="checkbox"/> Out of Calibration <input type="checkbox"/> Out of Sequence
<input type="checkbox"/> Outside Dimensions <input type="checkbox"/> Over/Under tolerance <input type="checkbox"/> Part Incorrect <input type="checkbox"/> Part Lost/Missing <input type="checkbox"/> Part Moved <input type="checkbox"/> Positioned Wrong <input type="checkbox"/> Power Loss/Surge		
<input type="checkbox"/> Pressure/Forced Set-up <input type="checkbox"/> Temperature/Cure <input type="checkbox"/> Weld <input type="checkbox"/> Wrong Stock Pulled <input type="checkbox"/> Other		

**Work Order ID 114930**

Monday, March 17, 2014 2:32:17 PM

**\*114930\***

Page 2

Item ID: D3535-23

Revision ID:

Item Name: Stainless Steel Wearplate Center Fwd

Start Date: 3/17/14

Start Qty: 24.00

**\*24\***

Required Date: 3/17/14

Req'd Qty: 24.00

**\*24\***

Reference:

Accept

**\*N900040100\***

Setup Start

**\*NS1\***

Stop

**\*NS2\***

Cust Item ID:

Customer:

Approvals:

Process Plan:

Date:

QC:

Date:

Tooling:

Date:

SPC (Y/N):

Date:

Run Start

**\*NR1\***

Stop

**\*NR2\***Sequence ID/  
Work Center IDOperation  
DescriptionSet Up/  
Run Hours

Tool ID

Tool #

Plan  
CodeAccept  
QtyReject  
QtyReject  
NumberInsp.  
Stamp

130

**\*130\***

Brake NC

Brake NC

NC BRAKE

Memo

1-Form on Brake as per Dwg D3535 using Jigs DT8261 and DT83262-Form  
joggle as per Dwg D3535 using Jig DT81583-Identify as D3535-23

0.00

DAS

30

9-89

26

DAS

36

9-89

14/03/24

0.00

140

**\*140\***

QC

Quality Control

QC5- Inspect part completeness to step on W/O

Memo

0.00

0.00

Smp  
14/3/25

26

150

**\*150\***

Powdercoat

Powder Coating

Grey Sandtex (Ref: 4.3.5.6) per QSI005 4.3

Memo

START TIME:

3:10

FINISH TIME:

OVEN TEMPERATURE:

31.40

0.00

0.00

26

φ

14-3-25

DAS  
34  
9-89

DQA: \_\_\_\_\_ Date: \_\_\_\_\_



## WORK ORDER NON-CONFORMANCE / UPDATE

QA Closed: \_\_\_\_\_ Date: \_\_\_\_\_

Work Order update only ☐

Work Order: _____  Part No. _____  NCR No. _____	<b>DISPOSITION</b>  Rework <input type="checkbox"/> Scrap <input type="checkbox"/> Use-as-is <input type="checkbox"/> Suspected Unapproved <input type="checkbox"/>	<b>AGAINST DEPARTMENT/PROCESS</b>  <table style="width:100%; border: none;"> <tr> <td>Skid-tube <input type="checkbox"/></td> <td>Crosstube <input type="checkbox"/></td> <td>Water Jet <input type="checkbox"/></td> <td>Engineering <input type="checkbox"/></td> </tr> <tr> <td>Machining <input type="checkbox"/></td> <td>Small Fab <input type="checkbox"/></td> <td>Prod. Eng. Coord. <input type="checkbox"/></td> <td>Quality <input type="checkbox"/></td> </tr> <tr> <td>Thermoforming <input type="checkbox"/></td> <td>Finishing <input type="checkbox"/></td> <td>Rec/Store/Packaging <input type="checkbox"/></td> <td>Other <input type="checkbox"/></td> </tr> <tr> <td>Large Fab <input type="checkbox"/></td> <td>Composite <input type="checkbox"/></td> <td>Supplier <input type="checkbox"/></td> <td></td> </tr> </table>	Skid-tube <input type="checkbox"/>	Crosstube <input type="checkbox"/>	Water Jet <input type="checkbox"/>	Engineering <input type="checkbox"/>	Machining <input type="checkbox"/>	Small Fab <input type="checkbox"/>	Prod. Eng. Coord. <input type="checkbox"/>	Quality <input type="checkbox"/>	Thermoforming <input type="checkbox"/>	Finishing <input type="checkbox"/>	Rec/Store/Packaging <input type="checkbox"/>	Other <input type="checkbox"/>	Large Fab <input type="checkbox"/>	Composite <input type="checkbox"/>	Supplier <input type="checkbox"/>	
Skid-tube <input type="checkbox"/>	Crosstube <input type="checkbox"/>	Water Jet <input type="checkbox"/>	Engineering <input type="checkbox"/>															
Machining <input type="checkbox"/>	Small Fab <input type="checkbox"/>	Prod. Eng. Coord. <input type="checkbox"/>	Quality <input type="checkbox"/>															
Thermoforming <input type="checkbox"/>	Finishing <input type="checkbox"/>	Rec/Store/Packaging <input type="checkbox"/>	Other <input type="checkbox"/>															
Large Fab <input type="checkbox"/>	Composite <input type="checkbox"/>	Supplier <input type="checkbox"/>																

Root Cause	Date	Step	Qty	Description of work order update or non-conformance	Initial Chief Eng	Action Description	Sign & Date	Verification	QC Inspector
Design									
Doc/Data									
Equip/Tooling									
Handling/Pre									
Material									
Operator									
Offset/Setup									
Process									
Supplier									
Training									
Transport									
Unapproved									

### FAULT CATEGORY

<b>Landing Gear</b> <input type="checkbox"/> Bending <input type="checkbox"/> Centre Not Concentric <input type="checkbox"/> Cracks <input type="checkbox"/> Crimp/Kink/Ripple/Wave <input type="checkbox"/> Cuffs <input type="checkbox"/> Crushing <input type="checkbox"/> Heat Treat <input type="checkbox"/> Inspection Strip in Tube <input type="checkbox"/> Marks/Chatter <input type="checkbox"/> Turning Sequence <input type="checkbox"/> Wave/Twist in Tube	<b>General</b> <input type="checkbox"/> Bend <input type="checkbox"/> BOM/Route <input type="checkbox"/> Broken/Damage/Defect <input type="checkbox"/> Burrs <input type="checkbox"/> Contamination <input type="checkbox"/> Countersink <input type="checkbox"/> Cut Too Short <input type="checkbox"/> Drawing <input type="checkbox"/> Drill Holes <input type="checkbox"/> Finish <input type="checkbox"/> Fit/Function	<input type="checkbox"/> Folio/Program <input type="checkbox"/> Grain <input type="checkbox"/> Hardware <input type="checkbox"/> Inspection Incomplete/Unqualified <input type="checkbox"/> Instructions Incomplete/Unclear <input type="checkbox"/> Misaligned/off center <input type="checkbox"/> Mislabeled <input type="checkbox"/> Misread <input type="checkbox"/> Off-set <input type="checkbox"/> Out of Calibration <input type="checkbox"/> Out of Sequence	<input type="checkbox"/> Outside Dimensions <input type="checkbox"/> Over/Under tolerance <input type="checkbox"/> Part Incorrect <input type="checkbox"/> Part Lost/Missing <input type="checkbox"/> Part Moved <input type="checkbox"/> Positioned Wrong <input type="checkbox"/> Power Loss/Surge  <input type="checkbox"/> Pressure/Forced <input type="checkbox"/> Set-up <input type="checkbox"/> Temperature/Cure <input type="checkbox"/> Weld <input type="checkbox"/> Wrong Stock Pulled <input type="checkbox"/> Other
--	--	---	--

**Work Order ID 114930**

Monday, March 17, 2014 2:32:17 PM

**\*114930\***

Page 3

Item ID: D3535-23

Revision ID:

Item Name: Stainless Steel Wearplate Center Fwd

Start Date: 3/17/14

Start Qty: 24.00

**\*24\***

Required Date: 3/17/14

Req'd Qty: 24.00

**\*24\***

Reference:

Accept

**\*N900040100\***

Setup Start

**\*NS1\***

Stop

**\*NS2\***

Cust Item ID:

Customer:

Approvals:

Process Plan: \_\_\_\_\_

Date: \_\_\_\_\_

QC: \_\_\_\_\_

Date: \_\_\_\_\_

Tooling: \_\_\_\_\_

Date: \_\_\_\_\_

SPC (Y/N): \_\_\_\_\_

Date: \_\_\_\_\_

Run Start

**\*NR1\***

Stop

**\*NR2\***Sequence ID/  
Work Center IDOperation  
DescriptionSet Up/  
Run Hours

Tool ID

Tool #

Plan  
CodeAccept  
QtyReject  
QtyReject  
NumberInsp.  
Stamp

160

QC3- Inspect Part Finish

0.00

**\*160\***

QC

Memo

0.00

Quality Control

X26 d JH 1403/26

170

Identify as per dwg &amp; Stock Location: 1712-00 0.00

0.00

**\*170\***

Packaging

Memo

0.00

Packaging

X26 d JH 1403/26

180

QC21- Final Inspection - Work Order Release

0.00

**\*180\***

QC

Memo

0.00

Quality Control

MLJ 14-03-26

MF  
14-3-26

DQA: \_\_\_\_\_ Date: \_\_\_\_\_



## WORK ORDER NON-CONFORMANCE / UPDATE

QA Closed: \_\_\_\_\_ Date: \_\_\_\_\_

Work Order update only ☐

Work Order: _____  Part No. _____  NCR No. _____	<b>DISPOSITION</b>  Rework <input type="checkbox"/> Scrap <input type="checkbox"/> Use-as-is <input type="checkbox"/> Suspected Unapproved <input type="checkbox"/>	<b>AGAINST DEPARTMENT/PROCESS</b>  <table style="width:100%;"> <tr> <td>Skid-tube <input type="checkbox"/></td> <td>Crosstube <input type="checkbox"/></td> <td>Water Jet <input type="checkbox"/></td> <td>Engineering <input type="checkbox"/></td> </tr> <tr> <td>Machining <input type="checkbox"/></td> <td>Small Fab <input type="checkbox"/></td> <td>Prod. Eng. Coord. <input type="checkbox"/></td> <td>Quality <input type="checkbox"/></td> </tr> <tr> <td>Thermoforming <input type="checkbox"/></td> <td>Finishing <input type="checkbox"/></td> <td>Rec/Store/Packaging <input type="checkbox"/></td> <td>Other <input type="checkbox"/></td> </tr> <tr> <td>Large Fab <input type="checkbox"/></td> <td>Composite <input type="checkbox"/></td> <td>Supplier <input type="checkbox"/></td> <td></td> </tr> </table>	Skid-tube <input type="checkbox"/>	Crosstube <input type="checkbox"/>	Water Jet <input type="checkbox"/>	Engineering <input type="checkbox"/>	Machining <input type="checkbox"/>	Small Fab <input type="checkbox"/>	Prod. Eng. Coord. <input type="checkbox"/>	Quality <input type="checkbox"/>	Thermoforming <input type="checkbox"/>	Finishing <input type="checkbox"/>	Rec/Store/Packaging <input type="checkbox"/>	Other <input type="checkbox"/>	Large Fab <input type="checkbox"/>	Composite <input type="checkbox"/>	Supplier <input type="checkbox"/>	
Skid-tube <input type="checkbox"/>	Crosstube <input type="checkbox"/>	Water Jet <input type="checkbox"/>	Engineering <input type="checkbox"/>															
Machining <input type="checkbox"/>	Small Fab <input type="checkbox"/>	Prod. Eng. Coord. <input type="checkbox"/>	Quality <input type="checkbox"/>															
Thermoforming <input type="checkbox"/>	Finishing <input type="checkbox"/>	Rec/Store/Packaging <input type="checkbox"/>	Other <input type="checkbox"/>															
Large Fab <input type="checkbox"/>	Composite <input type="checkbox"/>	Supplier <input type="checkbox"/>																

Root Cause	Date	Step	Qty	Description of work order update or non-conformance	Initial Chief Eng	Action Description	Sign & Date	Verification	QC Inspector
Design									
Doc/Data									
Equip/Tooling									
Handling/Pre									
Material									
Operator									
Offset/Setup									
Process									
Supplier									
Training									
Transport									
Unapproved									

### FAULT CATEGORY

<b>Landing Gear</b> <input type="checkbox"/> Bending <input type="checkbox"/> Centre Not Concentric <input type="checkbox"/> Cracks <input type="checkbox"/> Crimp/Kink/Ripple/Wave <input type="checkbox"/> Cuffs <input type="checkbox"/> Crushing <input type="checkbox"/> Heat Treat <input type="checkbox"/> Inspection Strip in Tube <input type="checkbox"/> Marks/Chatter <input type="checkbox"/> Turning Sequence <input type="checkbox"/> Wave/Twist in Tube	<b>General</b> <input type="checkbox"/> Bend <input type="checkbox"/> BOM/Route <input type="checkbox"/> Broken/Damage/Defect <input type="checkbox"/> Burrs <input type="checkbox"/> Contamination <input type="checkbox"/> Countersink <input type="checkbox"/> Cut Too Short <input type="checkbox"/> Drawing <input type="checkbox"/> Drill Holes <input type="checkbox"/> Finish <input type="checkbox"/> Fit/Function	<input type="checkbox"/> Folio/Program <input type="checkbox"/> Grain <input type="checkbox"/> Hardware <input type="checkbox"/> Inspection Incomplete/Unqualified <input type="checkbox"/> Instructions Incomplete/Unclear <input type="checkbox"/> Misaligned/off center <input type="checkbox"/> Mislabeled <input type="checkbox"/> Misread <input type="checkbox"/> Off-set <input type="checkbox"/> Out of Calibration <input type="checkbox"/> Out of Sequence	<input type="checkbox"/> Outside Dimensions <input type="checkbox"/> Over/Under tolerance <input type="checkbox"/> Part Incorrect <input type="checkbox"/> Part Lost/Missing <input type="checkbox"/> Part Moved <input type="checkbox"/> Positioned Wrong <input type="checkbox"/> Power Loss/Surge  <input type="checkbox"/> Pressure/Forced <input type="checkbox"/> Set-up <input type="checkbox"/> Temperature/Cure <input type="checkbox"/> Weld <input type="checkbox"/> Wrong Stock Pulled <input type="checkbox"/> Other  _____ _____ _____
--	--	---	---

# Picklist Print

Monday, March 17, 2014 2:32:17 PM

Page 1

Work Order ID: 114930

\*114930\*

Parent Item: D3535-23

\*D3535-23\*

Parent Item Name: Stainless Steel Wearplate Center Fwd

Start Date: 3/17/14

Required Date: 3/17/14

Start Qty: 24.00

Required Qty: 24.00

Comments: IPP Rev:A New Issue 07-02-15 JLM  
IPP Rev:B As per Rev B 07-08-31 JLM Verified By:EC

Component Item ID/ Item Name	Replacement Item ID	Mfg/ Purch	Bin Item	Primary Location	Last Location	Route Seq ID	Unit of Measure	Qty on Hand	Qty per Kit	Total Qty	Qty Issued	Date Issued	Status
---------------------------------	------------------------	---------------	-------------	---------------------	------------------	-----------------	--------------------	----------------	-------------	--------------	---------------	----------------	--------

M304S20GA Purchased No

100 sf 352.9019 1.3615

~~34.30579~~

**\*M304S20GA\***

\*\*

~~34.30579~~ (38.8)

mm

14-03-24

304/316 .040 Sheet

Location

Loc Qty

Loc Code

MAT020

352.9018948

m126852

0.91

m127454

60.3518948

m128315

4.4

m128435

287.24

(28435 - (38.8))

DQA: \_\_\_\_\_ Date: \_\_\_\_\_



## WORK ORDER NON-CONFORMANCE / UPDATE

QA Closed: \_\_\_\_\_ Date: \_\_\_\_\_

Work Order update only ☐

Work Order: _____  Part No. _____  NCR No. _____				<b>DISPOSITION</b>  Rework <input type="checkbox"/> Scrap <input type="checkbox"/> Use-as-is <input type="checkbox"/> Suspected Unapproved <input type="checkbox"/>		<b>AGAINST DEPARTMENT/PROCESS</b>  <div style="display: flex; justify-content: space-between;"> <div>           Skid-tube <input type="checkbox"/>            Machining <input type="checkbox"/>            Thermoforming <input type="checkbox"/>            Large Fab <input type="checkbox"/> </div> <div>           Crosstube <input type="checkbox"/>            Small Fab <input type="checkbox"/>            Finishing <input type="checkbox"/>            Composite <input type="checkbox"/> </div> <div>           Water Jet <input type="checkbox"/>            Prod. Eng. Coord. <input type="checkbox"/>            Rec/Store/Packaging <input type="checkbox"/>            Supplier <input type="checkbox"/> </div> <div>           Engineering <input type="checkbox"/>            Quality <input type="checkbox"/>            Other <input type="checkbox"/> </div> </div>					
Root Cause	Date	Step	Qty	Description of work order update or non-conformance	Initial Chief Eng	Action Description	Sign & Date	Verification	QC Inspector		
Design											
Doc/Data											
Equip/Tooling											
Handling/Pre											
Material											
Operator											
Offset/Setup											
Process											
Supplier											
Training											
Transport											
Unapproved											

FAULT CATEGORY			
<b>Landing Gear</b> <input type="checkbox"/> Bending <input type="checkbox"/> Centre Not Concentric <input type="checkbox"/> Cracks <input type="checkbox"/> Crimp/Kink/Ripple/Wave <input type="checkbox"/> Cuffs <input type="checkbox"/> Crushing <input type="checkbox"/> Heat Treat <input type="checkbox"/> Inspection Strip in Tube <input type="checkbox"/> Marks/Chatter <input type="checkbox"/> Turning Sequence <input type="checkbox"/> Wave/Twist in Tube	<b>General</b> <input type="checkbox"/> Bend <input type="checkbox"/> BOM/Route <input type="checkbox"/> Broken/Damage/Defect <input type="checkbox"/> Burrs <input type="checkbox"/> Contamination <input type="checkbox"/> Countersink <input type="checkbox"/> Cut Too Short <input type="checkbox"/> Drawing <input type="checkbox"/> Drill Holes <input type="checkbox"/> Finish <input type="checkbox"/> Fit/Function	<input type="checkbox"/> Folio/Program <input type="checkbox"/> Grain <input type="checkbox"/> Hardware <input type="checkbox"/> Inspection Incomplete/Unqualified <input type="checkbox"/> Instructions Incomplete/Unclear <input type="checkbox"/> Misaligned/off center <input type="checkbox"/> Mislabeled <input type="checkbox"/> Misread <input type="checkbox"/> Off-set <input type="checkbox"/> Out of Calibration <input type="checkbox"/> Out of Sequence	<input type="checkbox"/> Outside Dimensions <input type="checkbox"/> Over/Under tolerance <input type="checkbox"/> Part Incorrect <input type="checkbox"/> Part Lost/Missing <input type="checkbox"/> Part Moved <input type="checkbox"/> Positioned Wrong <input type="checkbox"/> Power Loss/Surge  <input type="checkbox"/> Pressure/Forced Set-up <input type="checkbox"/> Temperature/Cure <input type="checkbox"/> Weld <input type="checkbox"/> Wrong Stock Pulled <input type="checkbox"/> Other  _____ _____ _____



<b>DART AEROSPACE LTD</b>		<b>Work Order:</b>	114930
<b>Description:</b> Wearshoe		<b>Part Number:</b>	D3535-23
<b>Inspection Dwg:</b> D3535 <b>Rev:</b> B		<b>Page 1 of 1</b>	

### FIRST ARTICLE INSPECTION CHECKLIST

☒ First Article      ☐ Prototype

Drawing Dimension	Tolerance	Actual Dimension	Accept	Reject	Method of Inspection	Comments
1.885	+/-0.010	1.893"	—		✓	
2.000	+/-0.010	2.000"	—		✓	
4.750	+/-0.010	4.750"	—		✓	
9.500	+/-0.010	9.503"	—		✓	Jkm08
14.250	+/-0.010	14.250"	—		T	
17.750	+/-0.010	17.750"	—		T	
23.140	+/-0.010	23.140"	—		T	Jkm07
28.530	+/-0.010	28.530"	—		T	
33.920	+/-0.010	33.920"	—		T	
39.310	+/-0.010	39.310"	—		T	
44.700	+/-0.010	44.700"	—		T	
48.200	+/-0.010	48.200"	—		T	
52.850	+/-0.010	52.850"	—		T	
Ø0.188	+0.005/-0.001	0.190"	—		✓	Jkm05
48.00	+/-0.030	48.00"	—		T	
39.00	+/-0.030	39.00"	—		T	
32.00	+/-0.030	32.00"	—		T	
24.00	+/-0.030	24.00"	—		T	
16.00	+/-0.030	16.00"	—		T	
8.00	+/-0.030	8.00"	—		✓	
6.00	+/-0.030	6.006"	—		✓	
0.300	+/-0.010	0.304"	—		✓	
0.300	+/-0.010	0.302"	—		✓	
0.038	+/-0.010	0.039"	—		✓	

<b>Measured by:</b>	Jm	<b>Audited by:</b>	27 9-89	<b>Prototype Approval:</b>	N/A
<b>Date:</b>	14-03-23	<b>Date:</b>	14/5/24	<b>Date:</b>	N/A

Rev	Date	Change	Revised by	Approved
A	07.11.23	New Issue	KJ/EC/DD	







**DART**

RELEASED

07.04.24

114930.MCS  
1703-18

DESIGN	DRAWN BY	DART AEROSPACE USA, INC.		
CB	PH	PORT HADLOCK, WA		
CHECKED	APPROVED	DRAWING NO.	REV. B	
DATE		TITLE	SHEET 1 OF 7	SCALE
07.04.17		WEARSHOE		1:10
A	06.10.25	NEW ISSUE		
B	07.04.17	MOVE TAB OUTBOARD, ADD AMS SPEC		

**D3535-11F FLAT PATTERN****D3535-11 BEND DETAIL****D3535-13F FLAT PATTERN****D3535-13 BEND DETAIL****NOTES**



- 1) MATERIAL: AISI 304/316 SS SHEET PER AMS 5513 OR AMS 5524, 20 GAUGE (0.038 THICK) (REF DART SPEC M304S20GA)
- 2) FINISH: POWDER COAT GREY SANTEX (4.3.5.6) PER QSI 005 4.3
- 3) PART IS SYMMETRICAL ABOUT  $\phi$
- 4) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 5) ALL DIMENSIONS ARE IN INCHES
- 6) BREAK ALL SHARP EDGES TO 0.010 MAX
- 7) IDENTIFY WITH DART P/N USING WHITE FINE POINT PAINT MARKER
- 8) SEE PAGE 7 FOR DETAILS AND SECTION

**DART**

RELEASED



07.04.24 -H

DESIGN	CB	DRAWN BY	PH	DART AEROSPACE USA, INC.
CHECKED	<i>[Signature]</i>	APPROVED	<i>[Signature]</i>	PORT HADLOCK, WA
DATE	07.04.17	TITLE	WEARSHOE	REV. B
				SHEET 2 OF 7
				SCALE 1:10



**D3535-15F FLAT PATTERN**

**D3535-15 BEND DETAIL**



**D3535-21F FLAT PATTERN**

**D3535-21 BEND DETAIL**


**NOTES**

- 1) MATERIAL: AISI 304/316 SS SHEET PER AMS 5513 OR AMS 5524, 20 GAUGE (0.038 THICK) (REF DART SPEC M304S20GA)
- 2) FINISH: POWDER COAT GREY SANDETEX (4.3.5.6) PER QSI 005 4.3
- 3) PART IS SYMMETRICAL ABOUT C
- 4) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 5) ALL DIMENSIONS ARE IN INCHES
- 6) BREAK ALL SHARP EDGES TO 0.010 MAX
- 7) IDENTIFY WITH DART P/N USING WHITE FINE POINT PAINT MARKER
- 8) SEE PAGE 7 FOR DETAILS AND SECTION



RELEASED  
07.04.24


DESIGN	DRAWN BY	DART AEROSPACE USA, INC.
C.B.	A.H.	PORT HADLOCK, WA
CHECKED	APPROVED	DRAWING NO.
#	#	D3535
DATE	TITLE	SHEET 3 OF 7
07.04.17	WEARSHOE	SCALE 1:10



D3535-23F FLAT PATTERN



D3535-23 BEND DETAIL



D3535-25F FLAT PATTERN



D3535-25 BEND DETAIL

NOTES

- 1) MATERIAL: AISI 304/316 SS SHEET PER AMS 5513 OR AMS 5524, 20 GAUGE (0.038 THICK)  
(REF DART SPEC M304S20GA)
- 2) FINISH: POWDER COAT GREY SANDTEX (4.3.5.6) PER QSI 005 4.3
- 3) PART IS SYMMETRICAL ABOUT  $\phi$
- 4) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 5) ALL DIMENSIONS ARE IN INCHES
- 6) BREAK ALL SHARP EDGES TO 0.010 MAX
- 7) IDENTIFY WITH DART P/N USING WHITE FINE POINT PAINT MARKER
- 8) SEE PAGE 7 FOR DETAILS AND SECTION





Copyright © 2006 by DART Aerospace USA, Inc.  
THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL, AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART Aerospace USA, Inc.





RELEASED  
07.04.24



DESIGN	C.B.	DRAWN BY	PH	DART AEROSPACE USA, INC.
CHECKED	<i>[Signature]</i>	APPROVED	<i>[Signature]</i>	PORT HADLOCK, WA
DATE	07.04.17	DRAWING NO.	D3535	REV. B
		TITLE	WEARSHOE	SHEET 4 OF 7
		SCALE	1:10	




**NOTES**



- 1) MATERIAL: AISI 304/316 SS SHEET PER AMS 5513 OR AMS 5524, 20 GAUGE (0.038 THICK) (REF DART SPEC M304S20GA)
- 2) FINISH: POWDER COAT GREY SANTEX (4.3.5.6) PER QSI 005 4.3
- 3) PART IS SYMMETRICAL ABOUT  $\phi$
- 4) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 5) ALL DIMENSIONS ARE IN INCHES
- 6) BREAK ALL SHARP EDGES TO 0.010 MAX
- 7) IDENTIFY WITH DART P/N USING WHITE FINE POINT PAINT MARKER
- 8) SEE PAGE 7 FOR DETAILS AND SECTION

RELEASED  
07.04.24

DESIGN	C.B.	DRAWN BY	PH	DART AEROSPACE USA, INC.	
				PORT HADLOCK, WA	
CHECKED		APPROVED		DRAWING NO.	D3535
				SHEET 5 OF 7	
DATE	07.04.17			TITLE	WEARSHOE
				SCALE	1:10



### **D35.35-35F FLAT PATTERN**



**D35.35-37F FLAT PATTERN**



## NOTES

- 1) MATERIAL: AISI 304/316 SS SHEET PER AMS 5513 OR AMS 5524,  
20 GAUGE (0.038 THICK)  
(REF DART SPEC M304S20GA)
- 2) FINISH: POWDER COAT GREY SANDTEX (4.3.5.6) PER  
QSI 005 4.3
- 3) PART IS SYMMETRICAL ABOUT C
- 4) TOLERANCES ARE PER DART QSI 018 UNLESS  
OTHERWISE NOTED
- 5) ALL DIMENSIONS ARE IN INCHES
- 6) BREAK ALL SHARP EDGES TO 0.010 MAX
- 7) IDENTIFY WITH DART P/N USING WHITE FINE POINT  
PAINT MARKER
- 8) SEE PAGE 7 FOR DETAILS AND SECTION

**Copyright © 2006 by DART AEROSPACE USA, INC.**  
THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE USA, INC.

Copyright © 2006 by DART AEROSPACE USA, INC









**DART**

RELEASED

07.04.24

**D3535-39F FLAT PATTERN****D3535-39 BEND DETAIL****D3535-41F FLAT PATTERN****D3535-41 BEND DETAIL****NOTES**


- 1) MATERIAL: AISI 304/316 SS SHEET PER AMS 5513 OR AMS 5524, 20 GAUGE (0.038 THICK) (REF DART SPEC M304S20GA)
- 2) FINISH: POWDER COAT GREY SANDTEX (4.3.5.6) PER QSI 005 4.3
- 3) PART IS SYMMETRICAL ABOUT  $\phi$
- 4) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 5) ALL DIMENSIONS ARE IN INCHES
- 6) BREAK ALL SHARP EDGES TO 0.010 MAX
- 7) IDENTIFY WITH DART P/N USING WHITE FINE POINT PAINT MARKER
- 8) SEE PAGE 7 FOR DETAILS AND SECTION

DESIGN <b>CB</b>	DRAWN BY <b>PH</b>	DART AEROSPACE USA, INC. PORT HADLOCK, WA
CHECKED 	APPROVED 	DRAWING NO. <b>D3535</b>
DATE 07.04.17	TITLE WEARSHOE	REV. B SHEET 6 OF 7
	SCALE 1:10	




DESIGN <b>CB</b>	DRAWN BY <b>PH</b>	DART AEROSPACE USA, INC. PORT HADLOCK, WA	
CHECKED 	APPROVED 	DRAWING NO. D3535	REV. B SHEET 7 OF 7
DATE 07.04.17		TITLE WEARSHOE	SCALE 1:1


RELEASED  
07.04.24



**DETAIL B**



**DETAIL A**



**SECTION C-C**

Copyright © 2006 by DART AEROSPACE USA, INC.

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE USA, INC.

